



Republic of the Philippines
ILOILO SCIENCE AND TECHNOLOGY UNIVERSITY
Miagao Campus
 Miagao, Iloilo
 Tel Nos. 315-8164
 Fax No. 315-9755



SUPPLEMENTAL/BID BULLETIN
ADDENDUM No. 01

This supplemental/bid bulletin is being issued to further clarify the **technical specifications** of items for the **Construction and Completion of Various Buildings**

Project Reference Number : **MC-INFRA-2022-02-06**
 Location of the Contract : **ISAT U-Miagao Campus, Miagao, Iloilo**
 Fund : **Fund 164**
 Approved Budget : **PhP 2,465,232.00**

Please be informed of the **additional or corrected technical specifications** of the items, as follow;

Technical Specifications

Construction of Two Storey Supply Office

| FROM | | | TO | | |
|-------------|--|---|------------------|---|--|
| VI | THERMAL AND MOISTURE PROTECTION | | | | |
| | 1 | Roofing | 1 | Roofing | |
| | | 5/32ø Drill Bit (Dormer or equivalent) | | 5/32ø Drill Bit | |
| IX | CEILING | | | | |
| | 1 | Dropped Ceiling @ 0.4 O.C boothways | 1 | Dropped Ceiling @ 0.4 O.C boothways | |
| | | Ceiling Board 3/16 thk x4"x8" hardilite board | | Ceiling Board 3/16 thk x4' x 8' hardilite board | |
| X | GLASS CURTAINS/SLIDING WINDOW & ALL GLASS DOORS | | | | |
| | 1 | Glass Curtain | 1 | Glass Curtain | |
| | W2, W4, W5 | Glass curtain (1/2 glass blue w/ snap on and aluminum frames) and its complete accessories@ 4 units | W2, W4, W5 | Glass curtain (1/2 glass blue w/ 5mm snap on and aluminum frames) and its complete accessories@ 4 units | |
| | W6 | 0.6 x 0.6 Awning Window w/ 1/2" Thick Clear Glass in Aluminum Frame | W6 | 0.6 x 0.6 Awning Window w/ 5mm Thick Clear Glass in Aluminum Frame | |
| XII | 1 | Plumbing & Sanitary | 1 | Plumbing & Sanitary | |
| | | 1" PVC Water Pipe PVC | | 1" PVC Water Pipe | |
| XIII | PAINTING | | | | |
| | 2 | Concrete Wall (interior/exterior) | 2 | Concrete Wall (interior/exterior) | |
| | | Latex Tinting color thaw blue | | Latex Tinting color thalo blue | |
| XIV | ELECTRICAL | | | | |
| | | Main Panel Board 60 Amp main 2P CB w/ 6 branches, 4- 2P,20A CB, 2-2P, 15A CB | | Main Panel Board 60 Amp main 2P CB w/ 6 branches, 4- 2P,20A CB, 2-2P, 15A CB plug-in | |
| | | 11 watts LED square panel light | | 11 watts LED square panel light daylight | |
| | | 4 watts LED square pin light | | 4 watts LED square pin light warm white | |
| | | 3-gang switch concealed | | 3-gang switch concealed wide series | |
| | | 2-gang switch concealed | | 2-gang switch concealed wide series | |
| | | single switch concealed | | single switch concealed wide series | |
| | | 3-way switch concealed | | 3-way switch concealed wide series | |
| | | duplex C.O concealed | | duplex C.O concealed with ground wide series | |

Bids and Awards Committee

Email add: miagao.bac@isatu.edu.ph

Tel No.: 315-8164 loc 121


Mobile No.: 09554897732

Completion of Bldg. Q – Academic Building

| FROM | | TO | |
|------------|---|---|--|
| III | CONCRETE WORKS | | |
| | 1 | Lintel Beams | 1 |
| | | hacksaw blade (Lennox) | hacksaw blade |
| | 2 | Floor Slab (ground) 2500 psi | 2 |
| | | hacksaw blade (Lennox) | hacksaw blade |
| V | CEILING | | |
| | 1 | Dropped Ceiling @ 0.4 O.C boothways | 1 |
| | | Ceiling Board 3/16 thk x4"x8" hardilite board | Ceiling Board 3/16 thk x4' x 8' hardilite board |
| | | 5/32ø Drill Bit (Dormer) | 5/32ø Drill Bit |
| VII | DOORS & WINDOWS | | |
| | 1 | Doors | 1 |
| | | stained/varnished finish solid panel door w/ 2x6 door jamb w/1/4 thk clear glass transum w/ 4- 2x3 heavy duty loose pien hinges & heavy duty door lock (quickset) | stained/varnished finish solid panel door w/ 2 x 6 door jamb w/1/4 thk clear glass transum w/ 4- 2 x 3 heavy duty loose pien hinges & heavy duty door lock |
| | 2 | Windows | 2 |
| | | 2.4 x 1.8 double control w/ heavy duty alum frame w/ 1/4 thk clear glass leaves & 12mmø square bars outside grills (jelo plast) | 2.4 x 1.8 double control w/ heavy duty alum frame w/ 1/4 thk clear glass leaves & 12mmø square bars outside grills |
| | | 3.2 x 1.8 double control w/ heavy duty alum frame w/ 1/4 thk clear glass leaves & 12mmø square bars outside grills (jelo plast) | 3.2 x 1.8 double control w/ heavy duty alum frame w/ 1/4 thk clear glass leaves & 12mmø square bars outside grills |
| IX | PAINTING Works | | |
| | 2 | Concrete Wall (interior/exterior) | 2 |
| | | Latex Tinting color thaw blue | Latex Tinting color thalo blue |
| | | water proofing paint (flexibond) | water proofing paint |
| X | ELECTRICAL Works | | |
| | | 15 watts LED bulb w/receptacle | 15 watts LED bulb w/ 4"ø receptacle |
| | | 3-gang switch concealed | 3-gang switch concealed wide series |
| | | duplex C.O concealed | duplex C.O concealed with ground wide series |
| | | 2" x 4" utility box PVC (Atlanta) | 2" x 4" utility box PVC |
| XI | Minor Repair of Bldg Q (Academic Bldg) | | |
| | D | Formworks & Scaffoldings (all repair works) | D |
| | | 2 x 2 x 10 good Lumber | 2" x 2" x 10' good Lumber |
| | | 2 x 3 x 10 good Lumber | 2" x 3" x 10' good Lumber |
| | | 1/4' thick Ordinary Plywood | 1/4" thick Ordinary Plywood |
| | | 2-1/2" CWN | 2 1/2" CWN |
| | | 1-1/2" CWN | 1 1/2" CWN |

This Supplement Bid Bulletin shall form part of the Bidding Documents

For the guidance and information of all concerned.


ELY S. CIASICO, Ph. D.
 BAC Chairman